Royalty statement for work: Improvements to drains of roads next to Ayyappa Temple of jakkur layout and Improvements to drains of roads of jakkur layout in ward No.07 Byatarayanapura in ward No.07 Byatarayanapura

Sl No	Item No	Unit	Bill Qty	Coarse agggregate		Fine aggregate	
				Co-eff	Qty	Co-eff	Qty
2	PCC 1:4:8	cum	107.83	0.96	103.52	0.48	51.76
3	M20	cum	239.85	0.95	227.86	0.416	99.78
6	Plain cement concrete 1:2:4	cum	14.40	0.9	12.96	0.45	6.48
		Total			**344.33**		**158.02**

	Abstract	Qty	Rate/cum	Amount
1	Coarse Agggregates	344.334	108	37188.10
2	Fine aggregates	158.016	103	16275.65
		Total		**53463.75**

Asst. Executive Engineer
Project Division
Yelahanka Zone
Bangalore